Annex-E-2						
REPAIR AND REHABILITATION OF NASEER LABZANKI DEWAN KHARAN						
Estimate of Under Ground Water Tank						
S.NO	**DESCRIPTION**	**QUANTITY**	**UNIT**	**Brand Offered**	**Unit Price**	**Total Price**
1	**Excavation:** Excavation in foundation of buildings and bridges includinglayout, dressing, Earth refilling around structures with excavatedearth, watering & ramming lead upto 100 ft. (30m) & lift upto5 ft. (1.5m)	620	**CFT**			
2	**Plain Cement concrete 1:4:8** Providing and laying plain machine mixed cement concrete using coarse sand and crushed aggregate having maximum size upto 1- 1/2" (38mm) & down gauge in foundation including levelling, compacting and curing. (1:4:8)	20	**CFT**			
3	**Plain Cement concrete 1:2:4** Providing and laying (1:2:4) plain machine mixed cement concrete using coarse sand and crushed aggregate having maximum size upto 1- 1/2" (38mm) & down gauge in foundation including levelling, compacting and curing.	69.25	**CFT**			
3	**Brick Work**	178.5	**CFT**			
5	**Deformd steel bars:** Providing and laying first class solid burnt brick masonry (Brick Strength:1800psi-2000psi) including scaffolding, raking out joints and curing in ground floor superstructure and i/c cost of testing Upto 4.5" (115 mm) nominal thick brick work Cement sand 1 : 3	81.68	**kg**			
6	**Plaster Work:** Providing and laying 1/2" thick 1:3 plaster with cement sand machine mixed mortar, using approved quality screened sand, including all bends, corners, recesses and also including hacking the concrete surfaces and racking the masonry joints and providing 8" wide strip of wire mesh at masonry concrete joints, wetting the masonry surface and applying neeru base. All plaster to be finished smooth with steel float in true level, line and plumb and properly cured. All work to be completed as per, specifications and as directed by the Engineer.	383.25	**SFT**			
7	**Opening Cover:** S&F 18 SWG MS sheet Cover with angle iron frame 1.5"x1.5"x1/8" size 2.5x 2.5	4	**SFT**			
Total Amount(Inclusive of all Govt. applicable Taxes, Deliveries, Transportations and Installations, if any)						