Annex-H

INSTALLATION OF SOLARIZED DWSS SYSTEM AT GGHS HAJI BARKAT SIAOZAI, BESIMA WASHUK

BOQ OF SOLAR SYSTEM

S.NO	DESCRIPTION	QUANTITY	UNIT	Brand Offered	Unit Price	Total Price
1	Solar Panel 600 **Watt** A Grade Poly Crystalline (Chinees)	6.00	No			
2	Solar Submersible Pump set including Motor of Chines make, complete in all respects including all taxes Solar Submersible Pump Set, **4.5 HP**	1.00	No			
3	Supplying HDPE pipes density 700-960 kg/cu.m and carbon black contants > 2% with DIN-8074, 8075 or PS-3580:1997(rev.) ISO 9001-2000 pressure classification of PE -100 (black) for water PN-16 including specials and valves. **25 mm**	220.00	Rft			
4	Supply, Install, connect, test and commission of SOLAR INVERTER **4.5kw** (Chinese) & accessories	1.00	No			
5	Solar Mounting Frame Fixed	6.00	No			
6	Ac 4 Core Cable 4mm	220.00	Rft			
7	7/29 Cable For Panel Connections	180.00	Rft			
8	Safety Rope	250.00	Rft			
9	Fencing of Solar Plats	1.00	Job			
10	Supplying HDPE pipes density 700-960 kg/cu.m and carbon black contants > 2% with DIN-8074, 8075 or PS-3580:1997(rev.) ISO 9001-2000 pressure classification of PE -100 (black) for water PN-10 including specials and valves. 20 mm	1200.00	Rft			
11	Providing and fixing LDPE overhead tank manufactured by Dura or equivalent on top of any floor 300 gallons capacity	1.00	No			
12	Gate Valve 2"	1.00	No			
13	Bib Cocks	8.00	No			
14	Supply and Istallation of 01 Sign Board Complete in all Respect and as per IR Design.	1.00	No			
Total Amount(Inclusive of all Govt. applicable Taxes, Deliveries, Transportations and Installations, if any)						