Annex-G

Ground Water Tank at GOVT GHS MISKAN E KALAT KHARAN

S.NO	DESCRIPTION	QUANTITY	UNIT	Brand Offered	Unit Price	Total Price
1	**Excavation**					
	Earth work excavation undressed, lead upto 50 ft. (15m.) Manual (For Covered area of less than 250 sft) In shingle or gravel	80.00	Cft			
2	**PCC(1:4:8)**					
	Providing and laying plain machine mixed cement concrete using coarse sand and crushed aggregate having maximum size upto 1- 1/2" (38mm) & down gauge in foundation including levelling, compacting and curing. **(1:4:8)**	40.00	Cft			
3	**Earth Work Filling**					
	Manual (Maximum Area 250 Sft) Compaction of earthwork mixing, moisturing earth to optimum moisture content in layers for compaction	120.00	Cft			
4	**PCC(1:2:4)**					
	Providing and laying plain machine mixed cement concrete (1:2:4) using coarse sand and crushed aggregate having maximum size upto 1- 1/2" (38mm) & down gauge in foundation including levelling, compacting and curing.	111.97	Cft			
5	**Brick Masonry**					
	Providing and laying first class solid burnt brick masonry (Brick Strength:1800psi-2000psi) including scaffolding, raking out joints and curing in ground floor superstructure and i/c cost of testing upto 4.5" (115 mm) nominal thick brick work Cement sand 1 : 3	247.50	Cft			
6	**Plastering**					
	3/4 inch (19mm) thick cement plaster using Coarse Sand on walls and columns in basement, plinth and ground floor including making edges, corners and curing. using 1 : 3 Ratio.	432.00	Sft			
	Steel					
7	Providing, fabricating and laying deformed Grade 40 steel reinforcement (deformed bar) for all kinds of R.C.C work in foundation, plinth and ground floor including the cost of straightening, removal of rust, cutting, bending, binding, wastage and providing such over-laps as are not shown on the drawings. The cost of binding wire and cement concrete spacer blocks or chairs for binding and holding the reinforcement in position is inclusive upto 15 ft. (5m) height	150	Kg			
8	Gate Valve 2" Dia Kitz or equivalent	1.00	No			
9	Providing Iron Cover	4.00	Sft			
10	GI Bibcock With Accessories	3.00	No			
11	Providing of Flexible Transparent Garden Pipe 3/4" Inches 2.5mm Normal Size Pure Quality approved by Engineer in charge	300.00	Rft			
12	Sign Board	1.00	No			
Total Amount(Inclusive of all Govt. applicable Taxes, Deliveries, Transportations and Installations, if any)						