Annex- F

CONSTRUCTION OF TWO WASHROOM AT GOVT GIRLS HIGH SCHOOL SARAWAN UC SARAWAN KHARAN

BOQ of 2 New Washrooms Size 5'x5'x8'

S.NO	DESCRIPTION	QUANTITY	UNIT	Brand Offered	Unit Price	Total Price
1	**Excavation /Earth work**					
	Excavation in foundation of buildings and bridges including layout, dressing, refilling around structures with excavated earth, watering & ramming lead upto 100 ft. (30m) & lift upto5 ft. (1.5m)	**117.00**	**Cft**			
2	**PCC 1:4:8**					
	Providing and laying plain machine mixed cement concrete using coarse sand and crushed aggregate having maximum size upto 1- 1/2" (38mm) & down gauge in foundation including levelling, compacting and curing. (1:4:8)	**19.50**	**Cft**			
3	**Brick Masonry 1:3**					
	Providing and laying first class solid burnt brick masonry (Brick Strength:1800psi-2000psi) including scaffolding, raking out joints and curing in ground floor superstructure and i/c cost of testing Upto 4.5" (115 mm) nominal thick brick work Cement sand 1 : 3	**138.32**	**Cft**			
4	**Super Structure**					
	Providing and laying first class solid burnt brick masonry (Brick Strength:1800psi-2000psi) including scaffolding, raking out joints and curing in ground floor superstructure and i/c cost of testing Upto 4.5" (115 mm) nominal thick brick work Cement sand 1 : 3	**200**	**Cft**			
5	**PCC 1:2:4**					
	Providing and laying plain machine mixed cement concrete (1:2:4) using coarse sand and crushed aggregate having maximum size upto 1- 1/2" (38mm) & down gauge in foundation including levelling, compacting and curing.	**68.00**	**Cft**			
6	**Plaster 1:3**					
	3/4 inch (19mm) thick cement plaster using Coarse Sand on walls and columns in basement, plinth and ground floor including making edges, corners and curing. using 1 : 3 Ratio.	**595**	**sft**			
7	**Girder**	**12**	**Rft**			
	Mughal or equivalent					
8	**T-Iron (800 g) on Roof Top of Latrine**	**72**	**rft**			
9	**Roof Tiles (1' X 1')**	**72**	**sft**			
10	**Ceramic Tiles**					
	Providing and laying 1/4" to 3/8" (6mm to 9mm) thick Glazed/ Matt tiles of any colour and size in ground floor laid over 1" (25mm) thick cement sand mortar base including jointing and washing the tiles with white cement slurry of matching color by using color pigment and curing complete in all respect and as directed by Engineer in charge.	**84**	**Sft**			
11	**Distempering inner wall new surface , 3 coats**					
	Distempering with Berger/ ICI or equivalent synthetic vinyl emulsion paint of approved shade on old surface of walls and ceiling including dusting, sand papering and cleaning in basement and ground floor. Three coats (@ at least 1.75 Litre per 10 Sq.m)	**194**	**sft**			
12	**Weather Shield**					
	Applying weather resistant paint coating such as ICI weather shield, Berger weather coat or equivalent to interior or exterior walls or ceiling including supplying all labour, materials, scaffoldings and removal of debris etc. @ at least 3.50 litre per 10	**240**	**sft**			
13	**Paint**	**36**	**sft**			
	A- Sub Total					

Toilet Accessories						
S.NO	**DESCRIPTION**	**QUANTITY**	**UNIT**	**Brand Offered**	**Unit Price**	**Total Price**
14	Providing and fixing squatting type water closet(China) with integral treads ICL Boch/Karam Cera or approved equivalent make including cost of inlet pipe cistern and lid cistern kit, stop cock deluxe type and other accessories, fittings, brackets, PVC down pipe, rubber rings/washers, P-Trap 4",making requisite number of holes in walls, plinth and floor for pipe connection and making good with approved material complete in all respect and as directed by Engineer in charge	**2**	**No**			
15	Electric Work Completed in all respect and Specifications and as directed by the Engineer in charge.	**1**	**Job**			
16		**36**	**Sft**			
17	Ventilators (2 ft x 1 ft) / Jaali	**4**	**Sft**			
18	Providing and fixing domestic type water tank of fiber glass 300 Gallon (Double Ply) Dura or equivalent.	**1**	**No**			
19	S/F Polypropylene Random copolymer (PPRC) pipe (Popular, Turk Plast or equivalent) complete in all respect- 1 inch (25 mm) dia along with fittings.	**100**	**Rft**			
20	Providing and Installing PVC 4" pipe IIL, Dadex or equivalent make registered with PSQCA in tube well bore hole and/or laying, cutting, jointing and testing PVC pipe lines in trenches.	**50**	**Rft**			
21	Providing of Flexible Transparent Garden Pipe 3/4" Inches 2.5mm Normal Size Pure Quality approved by Engineer in charge	**200**	**Rft**			
22	Soakage Pit (3'dia x 20' deep) complete in all respect	**1**	**Job**			
23	RCC Soakage Pit Cover (4'x4'x0.25') complete in all respect	**1**	**Job**			
24	Provision of solar plates of 150 volt of Germany company to operate water motor pump including installation, fitting, jointing, fixing and connecting with all accessories along with steel frame made by angle iron as per engineer in charge and complete in all respect.	**1**	**No**			
25	supply and installation of solar motor pump complete in all respect	**1**	**No**			
26	Providing and fixing export quality Earthenware WASH BASIN manufactured by any approved company including cost of inlet pipe cistern and lid, cistern kit stop cock deluxe ,Earth ware Pedestal and other accessories, fittings material such as brackets PVC down pipe rubber rings / washers ,Basin pipes making requisite number of holes in walls plinth and floor for pipe connection and making good with approved material. Complete in all Respect And as per Engineer In charge.	**1**	**No**			
27	GI Bib Cocks	**4**	**No**			
28	Sign Board	**1**	**No**			
29	Transportation	**1**	**Job**			
B- Sub Total						
Total Amount(A+B) (Inclusive of all Govt. applicable Taxes, Deliveries, Transportations and Installations, if any						