

Annex-A						
CONSTRUCTION OF TWO WASHROOM AT GOVT GIRLS HIGH SCHOOL BASIMA UC BASIMA WASHUK						
BOQ of 2 New Washrooms Size 5'x5'x8'						
Sr #	Description	Quantity	Unit	Brand Offered	Unit Price	Total Price
1	Excavation /Earth work Excavation in foundation of buildings and bridges including layout, dressing, refilling around structures with excavated earth, watering & ramming lead upto 100 ft. (30m) & lift upto 5 ft. (1.5m)	117.00	Cft			
2	PCC 1:4:8 Providing and laying plain machine mixed cement concrete using coarse sand and crushed aggregate having maximum size upto 1- 1/2" (38mm) & down gauge in foundation including levelling, compacting and curing. (1:4:8)	19.50	Cft			
3	Brick Masonry 1:3 Providing and laying first class solid burnt brick masonry (Brick Strength:1800psi-2000psi) including scaffolding, raking out joints and curing in ground floor superstructure and i/c cost of testing Upto 4.5" (115 mm) nominal thick brick work Cement sand 1 : 3	138.32	Cft			
4	Super Structure Providing and laying first class solid burnt brick masonry (Brick Strength:1800psi-2000psi) including scaffolding, raking out joints and curing in ground floor superstructure and i/c cost of testing Upto 4.5" (115 mm) nominal thick brick work Cement sand 1 : 3	200	Cft			
5	PCC 1:2:4 coarse sand and crushed aggregate having maximum size upto 1- 1/2" (38mm) & down gauge in foundation including levelling, compacting and curing.	68.00	Cft			
6	Plaster 1:3 3/4 inch (19mm) thick cement plaster using Coarse Sand on walls and columns in basement, plinth and ground floor including making edges, corners and curing. using 1 : 3 Ratio.	595	Sft			
7	Girder	12	Rft			
8	T-Iron (800 g) on Roof Top of Latrine	72	Rft			
9	Roof Tiles (1' X 1')	36	Sft			
10	Ceramic Tiles Providing and laying 1/4" to 3/8" (6mm to 9mm) thick Glazed/ Matt tiles of any colour and size in ground floor laid over 1" (25mm) thick cement sand mortar base including jointing and washing the tiles with white cement slurry of matching color by using color pigment and curing complete in all respect and as directed by Engineer in charge.	84	Sft			
11	Distemping inner wall new surface , 3 coats Distemping with Berger/ ICI or equivalent synthetic vinyl emulsion paint of approved shade on old surface of walls and ceiling including dusting, sand papering and cleaning in basement and ground floor. Three coats (@ at least 1.75 Litre per 10 Sq.m)	194	Sft			
12	Weather Shield Applying weather resistant paint coating such as ICI weather shield, Berger weather coat or equivalent to interior or exterior walls or ceiling including supplying all labour, materials, scaffoldings and removal of debris etc. @ at least 3.50 litre per 10	275	Sft			
13	Paint	36	Sft			
A-Sub Total						
Toilet Accessories						

Sr #	Description	Quantity	Unit	Brand Offered	Unit Price	Total Price
14	Providing and fixing squatting type water closet(China) with integral treads ICL Boch/Karam Cera or approved equivalent make including cost of inlet pipe cistern and lid cistern kit, stop cock deluxe type and other accessories, fittings, brackets, PVC down pipe, rubber rings/washers, P-Trap 4",making requisite number of holes in walls, plinth and floor for pipe connection and making good with approved material complete in all respect and as directed by Engineer in charge	2	No			
15	Electric Work Completed in all respect and Specifications and as directed by the Engineer in charge.	1	Job			
16	S&F 18 SWG MS sheet door with angle iron frame 1.5"x1.5"x1/8" size 3'	36	Sft			
17	Ventilators (2 ft x 1 ft) / Jaali	4	Sft			
18	Providing and fixing domestic type water tank of fiber glass 300 Gallon (Double Ply) Dura or equivalent.	1	No			
19	S/F Polypropylene Random copolymer (PPRC) pipe (Popular, Turk Plast or equivalent) complete in all respect- 1 inch (25 mm) dia along with fittings.	100	Rft			
20	Providing and Installing PVC 4" pipe ILL, Dadex or equivalent make registered with PSQCA in tube well bore hole and/or laying, cutting, jointing and testing PVC pipe lines in trenches.	40	Rft			
21	Providing of Flexible Transparent Garden Pipe 3/4" Inches 2.5mm Normal Size Pure Quality approved by Engineer in charge	200	Rft			
22	Soakage Pit (3'dia x 20' deep) complete in all respect	1	Job			
23	RCC Soakage Pit Cover (4'x4'x0.25') complete in all respect	1	Job			
24	Providing and fixing export quality Earthenware WASH BASIN manufactured by any approved company including cost of inlet pipe cistern and lid, cistern kit stop cock deluxe ,Earth ware Pedestal and other accessories, fittings material such as brackets PVC down pipe rubber rings / washers ,Basin pipes making requisite number of holes in walls plinth and floor for pipe connection and making good with approved material. Complete in all Respect And as per Engineer In charge.	1	No			
25	GI Bib Cocks	4	No			
26	Providing and installation of NasGas Water Cooler as per following specifications complete in all respect including So Safe Filter,fitting and joint of pipes 65 Litre Capacity, Prime Copper Wrapped Steel Tank & Electric Fan Motor, Food Grade Non-Magnet Water Tank Prime Grade Insulation, Breeze Brand Condenser (With Protection Cover),	1	NO			
27	Providing and installation of Orient Flare 3 taps Grey glass door water dispenser with capacity of 3.5 L, stainless steel tank, refrigerator, child lock and instant cooling including fitting installation complete in all respect	1	No			
28	Construction of row tap stand post size of 10 feet Length 1 feet width and 8 feet height including green fibre shade of 10x4 with angle iron frame, Tile work, 2" PPRC pipe, jointing and fighting complete in all respect	1	job			
29	Stabilizer	1	No			
30	Sign Board	1	No			
B-Sub Total						
Total Amount(A+B)(Inclusive of all Govt. applicable Taxes, Deliveries, Transportations and Installations, if any						