

Annex-A-1						
REPAIR AND REHABILITATION OF KILLI HOLANGI TANK UC RASKOH DISTRICT KHARAN						
Sr #	Description	Quantity	Unit	Brand Offered	Unit Price	Total Price
1	Concrete Slab For Well	1	Job			
	Providing and laying of RCC concrete slab (6'*6'*0.5' for well cover including curing, compacting complete in all respect					
2	Solar Panel 600 Watt	6.00	No			
	Supply, Install, connect, test and commission of SOLAR PANEL (Chinese) & accessories.					
3	Solar Submersible (4.5 HP)	1.00	No			
	Providing and fixing at Site of Certified Solar Submersible Pumpset including Motor of Chinese Make, complete in all respects including all taxes.4.5 HP Pump Set					
4	Solar Inverter (3.5 KW)	1	No			
	Supply, Install, connect, test and commission of SOLAR Inverter (Chinese) & accessories.					
5	HDPE Pipe 50mm or 2"	50.00	Rft			
	Supplying HDPE pipes density 700-960 kg/cu.m and carbon black contents > 2% with DIN-8074, 8075 or PS-3580:1997(rev.) ISO 9001-2000 pressure classification of PE -100 (black) for water PN-16 including specials and valves. 25 mm					
6	DC Cable 4mm four Core	50.00	Rft			
	Supply, Install, connect, test and commission of CABLES & accessories. DC Cable Stranded and flexible insulated copper DC wires and cables must be used for all outdoor and indoor installations. voltage drop must not exceed 1% on DC side of the power inverter and 1.5% on AC side of the power inverter. The wiring that leads into the pole, protected in a PVC Spiral / Flexible conduit. External cables adapted to outdoor exposure as per IEC 60811.The outer insulation: sunlight (UV)-resistant and weather-					
7	DC Cable 2mm Single Core	50.00	Rft			
	Supply, Install, connect, test and commission of CABLES & accessories. DC Cable Stranded and flexible insulated copper DC wires and cables must be used for all outdoor and indoor installations. voltage drop must not exceed 1% on DC side of the power inverter and 1.5% on AC side of the power inverter. The wiring that leads into the pole, protected in a PVC Spiral / Flexible conduit. External cables adapted to outdoor exposure as per IEC 60811.The outer insulation: sunlight (UV)-resistant and weather-					
8	Solar Mounting Frame	4	No			
	Solar Mounting Frame made by angle Iron and girder complete in all respect as per engineer incharge					
9	Rope for submersible	50.00	Rft			
	Providing and installation of rope of any best quality strenght for submersible in all respect as per engineer incharge.					
10	Fiber Water Tank	1.00	NO			
	Providing and fixing domestic type water tank of fiber glass 500 Gallon (Double Ply) Dura or equivalent including with brick base of (5'*5'*2').					
11	HDPE Pipe 20mm"	800.00	Rft			
	Supplying HDPE pipes density 700-960 kg/cu.m and carbon black contents > 2% with DIN-8074, 8075 or PS-3580:1997(rev.) ISO 9001-2000 pressure classification of PE -100 (black) for water PN-10 including specials and valves. 20 mm					
Total Amount (Inclusive of all Govt. applicable Taxes, Transportations, Deliveries and Installation,if any)						