

### Annex-B-1

#### BOQ of Solar System

S.#	Description of Work	Quantity	Unit	Brand Offered	Unit Price	Total Price
1	Solar Panel 330 <b>Watt</b> A Grade Poly Crystalline (Chinees)	13.00	No			
2	Solar Submersible Pump set including Motor of Chines make, complete in all respects including all taxes Solar Submersible Pump Set, <b>7.5HP</b>	1.00	No			
3	Supplying HDPE pipes density 700-960 kg/cu.m and carbon black contants > 2% with DIN-8074, 8075 or PS-3580:1997(rev.) ISO 9001-2000 pressure classification of PE -100 (black) for water PN-16 including specials and valves. <b>50 mm</b>	200.00	Rft			
4	Supply, Install, connect, test and commission of SOLAR INVERTER <b>7.5kw</b> (Chinese) & accessories	1.00	No			
5	Solar Mounting Frame Fixed	10.00	No			
6	Ac 4 Core Cable 4mm	250.00	Rft			
7	7/29 Cable For Panel Connections	180.00	Rft			
8	Safety Rope	250.00	Rft			
9	Fencing of Solar Plats	1.00	Job			
<b>Total Amount (Inclusive of all Govt applicable Taxes, Deliveries, Transportations and Installation, if any</b>						