

**Annex B**

**Provision of 7 no`s PWD Shelter Materials in the districts of Usta Muhammad and Sohbatpur, Baluchistan.**

S.#	Item	Description	Quantity	Unit	Brand offered	Unit Price	Total Price
1	Cement	Provision of Ordinary Portland Cement Lucky cement/Felcon or Equivalent 50 Kg Beg.	62.00	No			
2	Sand	Locally available from Near By river beds free from clay content and organic material, well graded & clean.	271.00	Cft			
3	Gravel/Crash	Available from Near By Crush Plant free from impurities well graded/Crashed atleast 20 mm dia.	210.00	Cft			
4	Brick	provision of A/First Class Brick (Standard size 9" x 4.5" x 3") Compressive strengt of Brick shoud be between: 1500psi- 1800psi).	7276.00	No			
5	Steel Doors with angle iron frame(3.5'x7')	20 SWG MS machine pressed sheet Door with angle iron frame.L 1 1/2 " x 1 1/2 " x 1/4 " or L 38.1 mm x 38.1 mm x 6.4 mm, bolt ,hinges, 2 to 3 coats of oil paint complete in all aspects. Weight Not <35kg.	1.00	No			
6	Steel Window with angle iron frame (4'x4')	20 SWG MS machine pressed sheet Window with angle iron frame.L 1 1/2 " x 1 1/2 " x 1/4 " or L 38.1 mm x 38.1 mm x 6.4 mm, bolt ,hinges, 2 to 3 coats of oil paint complete in all aspects. Weight Not <25kg.	1.00	No			
7	Girder (14 Feet)	Steel Grider 6.83 feet length and with depth section of 6"x3.5" and 3.2 KG Mass per Feet or 10.498 Kg Mass per meter.	40.50	Rft			
8	Angel Iron	Providing Tee iron (2" X 2" X 0.236") 50 mm x 50 mm x 6mm @1.40 kg/Ft Or 4.6kg/M)	186.00	Rft			
9	Steel 3/8"	Providing Tor steel grade 60 having yeild strength equal to 60000 psi reinforcment for all kind of RCC work in foundation , plinth and ground floor including the cost of straightening , removal of rust , cutting bending	119.12	Kg			
10	Steel 1/2"	Providing Tor steel grade 60 having yeild strength equal to 60000 psi reinforcment for all kind of RCC work in foundation , plinth and ground floor including the cost of straightening , removal of rust , cutting bending	207.36	Kg			
11	Double Ply plastic 14'x16'	Double Ply plastic of good quality.	224.00	Sft			
12	Roof Tiles	Providing of PCC Roof Tiles (12" X 12"x 1") at top of Room/washroom.	195.00	No			
13	Provision and Fixing of Handrail as per Design	Providing and fixing 2'-9" high Stair hand railing comprising of 2.5" dia 16 gauge Stain Steel pipe hand rail fixed with 2.5" dia pipe blusters at specified distance fixed at top of steps with expansion bolts, 2 Nos. of 16 gauge 1" dia Stainless Steel pipes horizontally fixed with blusters, Complete in all respects	15.00	Rft			
14	Visibility Plate (2'x2')	Providing of Sign Board of Stainless steel (16 guage)	1.00	No			
<b>Total Amount Per PWD Shelter Material (including All Govt. Applicable Taxes, Delivery, Transportation and Installation if any).</b>							
<b>Grand Total Amount for 7 Shelters</b>							