

**Annexure-A+4****Rehabilitation of Govt Primary School Pakha Ghulam, UC Pakha Ghulam, Tehsil Chamkani, District Peshawar.****Construction of accessible pathways, ramps and railing for PWDs**

<b>S.No</b>	<b>Description</b>	<b>Unit</b>	<b>Qty</b>	<b>Brand Offered</b>	<b>Rate</b>	<b>Total Amount</b>
<b>1</b>	<b>Excavation</b>					
	Excavation in foundation of building, bridges etc. complete : in ordinary soil	Cft	90.00			
<b>2</b>	<b>PCC 1:4:8</b>					
	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:4:8)	Cft	22.50			
<b>3</b>	<b>Plaster Ratio 1:4</b>					
	Cement Plaster 1:4, upto 20' height 1/2" thick including curing, good finishing, scaffolding complete in all respect.	Sft	240.00			
<b>4</b>	<b>Tuff Tiles</b>					
	Providing and Fixing Precast Concrete 5000 psi TUFF Tiles 50mm thick over bed of 2" thick sand	Sft	1620.00			
<b>Grand Total (Inclusive of All Govt. Applicable Taxes, labour, material supply, loading/unloading, Transportation and Installation, if any)</b>						