

Annexure-B+1

Rehabilitation of Govt Girls Community Model School (GGCMS) , Esa Khel Topchian District & Tehsil Peshawar

Rehabilitation/Repair of existing latrines

S.No	Description	Unit	Qty	Brand Offered	Rate	Total Amount
2	Rehabilitation and Repair of Existing Latrine Blocks					
1	Distemper					
	Distemping Old surface : Two coats	Sft	330.00			
2	Snowcem / Weathershield work					
	Preparing surface & painting with snowcem / weathershield paint : 2nd & subsequent coats complete in respect and direction of engineer in charge	Sft	610.18			
3	PLUMBING WORK					
i.	Providing and fitting glazed earthenware water closet (WC), squatter type (orisa pattern) combined with foot rest. complete in all respects : White	Each	1			
ii.	Providing and Fixing Plastic low down flushingb cistern 3 gallons (13.63 Liters) capacity including bracket set, copper connection, etc. complete in all respects: White (Best Quality)	Each	1			
iii.	Providing and fixing chromium plated (CP) bib-cock heavy duty of approved quality : 1.5 cm 1/2"	Each	2			
iv.	P-Trap (uPVC) for squatting type WC 4"	Each	1			
v.	uPVC floor Cleanout including 2 No. 45o elbows, transition pipe, SS screwed plug/cover assembly jointed air-tight with pipe, breaking concrete or masonry work & then making it good, etc. complete in all respects. (ii) 4" dia	Each	1			
vi.	Cowel on vent pipes of the following diameter. (i) 3"	Each	1			
vii.	Supplying and Fixing UPVC soil waste and vent pipe class B : 3" dia complete in all respect.	Rft	13			
4	Electrification work					
i.	Wiring of light/fan/call-bell point in 3/0.029" PVC insulated bare cable in PVC pipe/duct recessed	Each	5.00			
ii.	Supply at site, installation, testing and commissioning of the Two gang light control switches 10 Amps, 250Volts one way, including appropriate size concealed/ MS, powder coated back box, complete in all respects.	Each	5.00			
iii.	Supply and Erection of AC ENERGY EFFICIENT LED LIGHT BULBS (7-16 W) with lamp holder. Complete in all	Each	5.00			
Grand Total (Inclusive of All Govt. Applicable Taxes, labour, material supply, loading/unloading, Transportation and Installation, if any)						