

**Annexure-B+2**

**Rehabilitation of Govt Girls Community Model School (GGCMS) , Esa Khel Topchian District & Tehsil Peshawar.**

**Construction of new latrines**

S.No	Description	Unit	Qty	Brand Offered	Rate	Total Amount
<b>3.A</b>	<b>Cleaning of Sweptic tank</b>					
<b>1</b>	<b>Cleaning of septic tank</b>					
	Cleaning of septic tank including disposal of waste	Cft	336.00			
<b>2</b>	<b>Brick Masonry in Septic Tank</b>					
	Providing and laying 1st class brick work in foundation and plinth in Cement, sand mortar 1:5, including curing, placing complete in all respect.	Cft	71.25			
<b>3</b>	<b>Backfill</b>					
	Filling, watering and ramming earth under floor and around tank with surplus earth from foundation/lawn, etc	Cft	144.00			
<b>4</b>	<b>Plaster Ratio 1:4</b>					
	Cement plaster 1:4 1/2" thick including good finishing and curing complete in all respect.	Sft	95.00			
<b>5</b>	<b>Mosaic dado</b>					
	Mosaic dado or skirting complete as per specs Using grey cement : 3/8" thick. including curing and finishing, as directed by the Engineer In Charge.	Sft	95.00			
	<b>Sub Total Amount for the Septic Tank: 3.A</b>					
<b>3.B</b>	<b>Construction of Two New Latrines</b>					
<b>1</b>	<b>Excavation</b>					
	Excavation in foundation of building, bridges etc. complete : in ordinary soil	Cft	408.00			
<b>2</b>	<b>PCC 1:4:8 in Folundation</b>					
	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:4:8)	Cft	34.00			
<b>3</b>	<b>1st Class Brick Masonary in foundation</b>					
	Providing and laying 1st class brick work in foundation and plinth in Cement, sand mortar 1:5, including curing, placing complete in all respect.	Cft	140.25			
<b>4</b>	<b>DPC 1:2:4</b>					
	Damp proof course of cement concrete 1:2:4 including bitumen coat, 1 layer polythene & 1 coat bitumen (2" thick).including shuttering, placing, finishing , curing complete with all respect.	Sft	64.13			
<b>5</b>	<b>Brick work in above FFI</b>					
	Providing and laying 1st class brick work upto 10 ft.height : Cement, sand mortar 1:6 including Grooved / V-Pointing, scaffolding and curing. Complete in all respect.	Cft	224.44			
<b>6</b>	<b>Backfill</b>					
	Filling, watering and ramming earth under floor with surplus earth from foundation/ flooring, etc	Cft	104.00			
<b>7</b>	<b>RCC Concrete 1:2:4</b>					
	RCC in roof slab, beam, column & other structural members, insitu or precast. (1:2:4). including shuttering, scaffolding, placing, finishing, competing, and curing complete in all respect.	Cft	67.09			
<b>8</b>	<b>Steel grade 40</b>					
	Supply & fabricate M.S. reinforcement for cement concrete (Hot rolled deformed bars Grade 40). including cutting, binding and laying complete in all respect.	Kg	128.00			
<b>9</b>	<b>Plaster Ratio 1:5</b>					
	Cement Plaster 1:5, upto 20' height 3/4" thick including curing, good finishing, scaffolding complete in all respect.	Sft	431.00			
<b>10</b>	<b>Floor &amp; Wall Tile</b>					

**Annexure-B+2**

**Rehabilitation of Govt Girls Community Model School (GGCMS) , Esa Khel Topchian District & Tehsil Peshawar.**

**Construction of new latrines**

S.No	Description	Unit	Qty	Brand Offered	Rate	Total Amount
	Providing and laying of white / light colour / glazed / non-skid tiles (size exceeding 400 sq cm but not exceeding 900 sq cm each) on walls and floors, complete over 1:3 cement mortar base (1/2"), set in neat cement paste, and joints grouted with white/coloured cement, complete in all respects. (Pak made)	Sq.m	34.29			
<b>11</b>	<b>Distemper</b>					
	Distemping New surface : Two coats	Sft	263.00			
<b>12</b>	<b>Snowcem / Weathershield work</b>					
	Preparing surface & painting with snowcem / weathershield paint : 2nd & subsequent coats complete in respect and direction of engineer in charge	Sft	297.00			
<b>13</b>	<b>Steel Door</b>					
	Supply, fabrication, and fixing of Bathroom MS Door with frame made of 16 SWG MS sheet for shutter, 1.5" x 1.5" x 3/16" angle iron frame, including iron hinges, tower bolt, handle, and painting with red oxide primer and two coats of synthetic enamel paint, complete in all respects.	Sft	38.5			
<b>14</b>	<b>Railing for Ramp</b>					
	Supply and fixing of fancy type stainless steel chromium plate 2" dia pipes stair railing 3/4" dia pipe fixed on specified space on steps in horizontal positions, complete in all respects as per design, drawing and satisfaction of engineer in-charge	Rft	25.00			
<b>15</b>	<b>PLUMBING WORK</b>					
i.	Providing and Fixing glazed earthen ware WC European type of approved size excluding cost of seat & cover, complete in all respects: White	Each	1			
ii.	Providing and fitting glazed earthenware water closet (WC), squatter type (orisa pattern) combined with foot rest. complete in all respects : White	Each	1			
iii.	Providing and Fixing glazed earthen ware wash hand basin (WHB) complete size 56x40 cm (22"x16"), including bracket set, waste coupling, complete in all respects: White with pedestal (Normal Quality)	Each	5			
iv.	Providing and Fixing glazed earthen ware wash hand basin (WHB) complete size 56x40 cm (22"x16"), including bracket set, waste coupling, complete in all respects: White without pedestal (Normal Quality) (especially for disabled person)	Each	2			
v.	Providing and Fixing Plastic low down flushing cistern 3 gallons (13.63 Liters) capacity including bracket set, copper connection, etc. complete in all respects: White (Best Quality)	Each	1			
vi.	Providing & fixing chromium plated double bib-cock with Muslim Shower of approved quality Complete is all respects.	Each	1			
vii.	Providing and fixing Providing and Fixing of Bath accessories set (chromium plated (C) soap dish, CP toilet paper holder, towel rail, best quality looking glass 5 mm thick neatly fitted with Mirror 60 x 45 cm (24"x18") size, glazed earthenware shelf (60x13 cm) 24"x5" with chromium plated (CP) brackets & railing) complete in all respect	Each	2			
viii.	Providing and fixing chromium plated (CP) tee stop cock 1.5 cm (1/2") of approved quality	Each	5			
ix.	Providing and fixing Grab bar (ROCA make) with W.C of special person's toilet including all fittings with complete installation.	No	1			

**Annexure-B+2**

**Rehabilitation of Govt Girls Community Model School (GGCMS) , Esa Khel Topchian District & Tehsil Peshawar.**

**Construction of new latrines**

<b>S.No</b>	<b>Description</b>	<b>Unit</b>	<b>Qty</b>	<b>Brand Offered</b>	<b>Rate</b>	<b>Total Amount</b>
x.	Providing and fixing chromium plated (CP) bib-cock heavy duty of approved quality : 1.5 cm 1/2"	Each	2			
xi.	Providing and fixing chromium plated (CP) or brass oxidized swan-neck cock 12 mm (1/2") dia of approved quality: Single way	Each	7			
xii.	P-Trap (uPVC) for squatting type WC 4"	Each	4			
xiii.	uPVC floor Cleanout including 2 No. 45o elbows, transition pipe, SS screwed plug/cover assembly jointed air-tight with pipe, breaking concrete or masonry work & then making it good, etc. complete in all respects. (ii) 4" dia	Each	4			
xiv.	Cowel on vent pipes of the following diameter. (i) 3"	Each	2			
xv.	Supplying and Fixing UPVC soil waste and vent pipe class B : 3" dia complete in all respect.	Rft	30			
xvi.	Providing, laying, cutting, jointing, testing and disinfecting UPVC pressure pipeline in trenches (conforming to BS 3505 manufactured ) jointed with socket, elbow, tee, bend and plug bend etc.manufactured by the respective manufacturer complete as per specifications UPVC Pressure Pipes Class B (6 Bar) i/n excavation. 4" Nominal Pipe Size (NPS)	Rft	52			
xvii.	Supply and Fixing of CP floor Truff Jalli with Grating 6"x6" complete in all respect.	Each	2			
xviii.	Providing, laying, cutting, jointing, testing and disinfecting UPVC pressure pipeline in trenches (conforming to BS 3505 manufactured ) jointed with socket, elbow, tee, bend and plug bend etc. manufactured by the respective manufacturer complete as per specifications UPVC Pressure Pipes Class B (6 Bar) i/n excavation. 6" Nominal Pipe Size (NPS)	Rft	52			
xix.	Providing, laying cutting, jointing, testing PPRC pipeline in walls/trenches with pipes (confirming to DIN 8077/8078, PN 20 of approved quality & fittings conforming to DIN 16962,PN25 of the same manufacturer) for cold/hot water supply systems including specials complete in all respect as per specifications: i/n excavation 3/4" i/d	Rft	80			
xx.	Providing, laying cutting, jointing, testing PPRC pipeline in walls/trenches with pipes (confirming to DIN 8077/8078, PN 20 of approved quality & fittings conforming to DIN 16962,PN25 of the same manufacturer) for cold/hot water supply systems including specials complete in all respect as per specifications: i/n excavation 1" i/d	Rft	150			
xxi.	Providing and fixing gun metal peet / gate valve (screwed) 25 mm (1") dia of approved quality.	Each	1			
<b>16</b>	<b>Electrification work</b>					
i.	Supply and Erection PVC pipe for wiring purpose complete Recessed in walls including chase etc : 1/2" i/d	Rft	50			
ii.	Wiring of light/fan/call-bell point in 3/0.029" PVC insulated bare cable in PVC pipe/duct recessed	Each	2			
iii.	Supply and Erection single core PVC insulated copper conductor 250/440 V grade cable : 7/0.029"	Rft	40			
iv.	Supply at site, installation, testing and commissioning of the Two gang light control switches 10 Amps, 250Volts one way, including appropriate size concealed/ MS, powder coated back box, complete in all respects.	Each	2			
v.	Supply and Erection of AC ENERGY EFFICIENT LED LIGHT BULBS (7-16 W) with lamp holder. Complete in all	Each	2			
<b>Sub Total Amount for the Construction of Two New Latrines : 3.B</b>						

**Annexure-B+2**

Rehabilitation of Govt Girls Community Model School (GGCMS) , Esa Khel Topchian District & Tehsil Peshawar.

Construction of new latrines

S.No	Description	Unit	Qty	Brand Offered	Rate	Total Amount
	<b>Grand Total : (3.A + 3.B) (Inclusive of All Govt. Applicable Taxes, labour, material supply, loading/unloading, Transportation and Installation, if any)</b>					