

Annexure-B+4**Rehabilitation of Govt Girls Community Model School (GGCMS) , Esa Khel Topchian District & Tehsil Peshawar****Construction of accessible pathways, ramps and railing for PWDs**

S.No	Description	Unit	Qty	Brand Offered	Rate	Total Amount
1	Earth Filling					
	Earth fill in lawns including dressing & compaction with suitable earth borrowed.	Cft	4457.25			
2	Pre-cast parabolic segments					
	Providing and laying Pre-cast parabolic segments, molded with cement concrete 1:1.5:3, 2" wall thickness including lowering in water channels to correct alignment and grade, jointing, finishing where necessary, and Filling of joints with cement sand mortars 1:4 with neat and clean finishing complete in all respect. Class "F " having top width 14", Depth 9" , length 48",	Rft	100.00			
3	Tuff Tiles					
	Providing, Fixing, leveling and compacting Precast Concrete 5000 psi TUFF Tiles 50mm thick over bed of 2" thick sand complete in all respect as per instructions of Engineer incharge	Sft	3119.25			
Grand Total (Inclusive of All Govt. Applicable Taxes, labour, material supply, loading/unloading, Transportation and Installation, if any)						