

Annexure-C+4

Rehabilitation of Govt Girls Primary School Pakha Ghulam, UC Pakha Ghulam, Tehsil Chamkani, District Peshawar.

Construction of accessible pathways, ramps and railing for PWDs

S.No	Description	Unit	Qty	Brand Offered	Rate	Total Amount
1	Excavation					
	Excavation in foundation of building, bridges etc. complete : in ordinary soil	Cft	18.00			
2	PCC 1:4:8					
	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:4:8)	Cft	4.50			
3	Brick work					
	Providing and laying 1st class brick work in foundation and plinth in Cement, sand mortar 1:5, including curing, placing complete in all respect.	Cft	58.50			
4	Backfill					
	Filling, watering and ramming earth under floor with surplus earth from foundation/ flooring, etc	Cft	72.00			
5	PCC 1:2:4					
	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:2:4) complete in all respect	Cft	12.00			
6	Floor & Wall Tile					
	Providing and laying of white / light colour / glazed / non-skid tiles (size exceeding 400 sq cm but not exceeding 900 sq cm each) on walls and floors, complete over 1:3 cement mortar base (1/2"), set in neat cement paste, and joints grouted with white/coloured cement, complete in all respects. (Pak made)	Sq.m	18.96			
7	Plaster Ratio 1:4					
	Cement Plaster 1:4, upto 20' height 1/2" thick including curing, good finishing, scaffolding complete in all respect.	Sft	83.00			
8	Railing for Ramp					
	Supply and fixing of fancy type stainless steel chromium plate 2" dia pipes stair railing 3/4" dia pipe fixed on specified space on steps in horizontal positions, complete in all respects as per design, drawing and satisfaction of engineer in-charge	Sft	18.00			
9	PPRC pipe					
	Providing, laying cutting, jointing, testing PPRC pipeline in walls/trenches with pipes (confirming to DIN 8077/8078, PN 20 of approved quality & fittings conforming to DIN 16962,PN25 of the same manufacturer) for cold/hot water supply systems including specials complete in all respect as per specifications: i/n excavation 3/4" i/d	Rft	20.00			
10	Providing and fixing chromium plated (CP) bib-cock heavy duty of approved quality : 1.5 cm 1/2"	Each	5.00			
11	Providing, laying, cutting, jointing, testing and disinfecting UPVC pressure pipeline in trenches (conforming to BS 3505 manufactured) jointed with socket, elbow, tee, bend and plug bend etc.manufactured by the respective manufacturer complete as per specifications UPVC Pressure Pipes Class B (6 Bar) i/n excavation. 4" Nominal Pipe Size (NPS)	Rft	20.00			
12	Supply and Fixing of CP floor Truff Jalli with Grating 6"x6" complete in all respect.	Each	1.00			
13	P-Trap (uPVC) for squatting type WC 4"	Each	1.00			
14	Providing and fixing best quality looking glass 5 mm thick neatly fitted on masonry wall etc. as per instruction of Engineer In-charge complete. Mirror 60 x 45 cm (24"x18") size	Each	5.00			
15	Providing and fixing choricum plated soap dish complete.	Each	3.00			

Annexure-C+4

Rehabilitation of Govt Girls Primary School Pakha Ghulam, UC Pakha Ghulam, Tehsil Chamkani, District Peshawar.

Construction of accessible pathways, ramps and railing for PWDs

S.No	Description	Unit	Qty	Brand Offered	Rate	Total Amount
Grand Total (Inclusive of All Govt. Applicable Taxes, labour, material supply, loading/unloading, Transportation and Installation, if any)						