

Annexure-D+3

Rehabilitation of Govt Girls High School Pakha Ghulam, UC Pakha Ghulam, Tehsil Chamkani, District Peshawar.

Construction of accessible pathways, ramps and railing for PWDs

S.No	Description	Unit	Qty	Brand Offered	Rate	Total Amount
5	Construction of accessible pathways, ramps and railing for PWDs					
1	Backfilling					
	Filling, watering and ramming earth under floor with surplus earth from foundation/ flooring, etc	Cft	45.00			
2	PCC 1:4:8					
	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:4:8) complete in all respect.	Cft	30.00			
3	PCC 1:2:4					
	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:2:4) complete in all respect	Sft	15.00			
4	Brick work					
	Providing and laying 1st class brick work upto 20 ft.height : Cement, sand mortar 1:6 including scaffolding and curing. Complete in all respect.	Cft	83.50			
Grand Total (Inclusive of All Govt. Applicable Taxes, labour, material supply, loading/unloading, Transportation and Installation, if any)						