

Annexure-A					
Supply of material and Construction of Bamboo Nursery Tunnel					
Size: 50 ft Length × 12 ft Width × 6.5 ft Height					
Sr#	Description	Unit	Qty	Unit Rate	Amount
1	3–4" Treated & Well Seasoned Bamboo Poles (11 Hoops @ 25 ft avg.)	Rft	300		
2	3" Treated & Well Seasoned Bamboo Ridge Pole	Rft	50		
3	2½" Treated & Well Seasoned Bamboo Side Members	Rft	100		
4	Cross Bracing Bamboo (Treated & Well Seasoned)	Rft	120		
5	GI Wire Binding	Kg	10		
6	Nylon Rope	Kg	5		
7	Nuts, Bolts, Fasteners	LS	1		
8	UV Stabilized Greenhouse Film (200 Micron)	Sq.ft	700		
9	Anchor Pegs (16mm × 24")	Nos	22		
10	Excavation & Backfilling	LS	1		
11	Fabrication & Installation Labour	LS	1		
12	Tools & Consumables	LS	1		
13	Painting/Preservative Treatment over Treated & Well Seasoned Bamboos	LS	1		
Total amount for single (01) Bamboo Nursery Tunnel					
Grand Total for 10 No's Bamboo Nursery Tunnel (Inclusive of all Govt. Applicable taxes, Transportation, Deliveries, Packing and Loading/ Unloading and installation, If any)					