ISLAMIC RELIEF PAKISTAN

Project: GRADUATING WITH RESILIENCE INITIATIVES TO TACKLE POVERTY (GRIP)- KP in Tehsil Mathra District Peshawar.

Rehabilitation and Installation of Solar System in Janazgah and Madrassa in Tehkal District Peshawar-Annexure-A

S #	Items & Specification	Brand Name	Quantity	Unit	Unit Rate	Amount-PKR
1	**Excavation/Drilling holes for concrete pedestals/foundations for elevated solar-panel supporting structure, including dressing of sides and disposal of surplus excavated material within the specified lead.**					
a	Excavation open cut upto 1.5m depth fordrains, pipes etc. & disposal for Sign board		30.00	Cft		
2	**Providing and laying PCC 1:4:8 or the mix specified by the approved design, including mixing, placing, compacting and curing below the foundation/pedestals.**					
a	PCC 1:4:8		10.00	Cft		
3	**Providing and fixing galvanized anchor bolts, nuts, washers and embedded fixing arrangements for securing the solar support legs to concrete pedestals.**					
a	Anchor Bolts		2.00	Job		
4	**Scraping and cleaning four existing main gates, removing loose paint and rust, applying one coat of anti-corrosive metal primer and two coats of approved weather-resistant enamel paint, complete.**					
a	Paint work main Gate of Janazgah		840.00	Sft		
a	Paint work on the main gate of Madrassa		160.00	Sft		
5	**Fabricating, supplying and installing mild-steel staircase railing, approximately 30 Rft, including posts, top handrail, intermediate members, base plates, anchor fasteners, welding, grinding, anti-corrosive primer and two coats of enamel paint.**					
a	Staircase railing in Janazgah and Madrassa		240.00	Sft		
6	**Providing, fabricating and fixing aluminium-framed glazed window, Premium Model, using approved-quality aluminium sections of 2.00 mm thickness and 3-inch (76 mm) section, including 5 mm thick clear float glass securely fixed with suitable glazing beads and rubber gaskets. The work shall include aluminium frame and shutters, hinges, handles, locking arrangements, screws, fasteners, rubber seals, silicone sealant, fixing brackets and all necessary accessories, including installation, alignment, adjustment and sealing of joints, complete in all respects as directed by the Engineer In-Charge.**					
a	windows in Madrassa		96.00	Sft		
7	**Providing and applying approved-quality distemper of approved colour on interior plastered wall and ceiling surfaces, including preparation and cleaning of the surface, removal of loose material, application of the specified primer/undercoat where required, and application of two uniform coats of distemper to achieve an even colour and finish, complete in all respects as directed by the Engineer In-Charge**					
a	Distemper		2000.00	Sft		
8	**Preparing surface and applying approved-quality Weather Shield Paint (ICI Dulux, Berger, Nippon or equivalent) on external plastered walls and concrete surfaces, including thorough cleaning, scraping and removal of loose paint, dust and other foreign materials, preparation of the surface, filling of minor cracks and surface imperfections with approved exterior-grade filler, and application of two uniform coats of Weather Shield Paint in approved colour and shade, complete in all respects as per CSR/MRS specifications and directions of the Engineer In-Charge.**					
a	Weather Shield		3000.00	Sft		
9	**Brick masonry work in superstructure up to 10 ft height in cement sand mortar 1:4**					
a	Brick work for Signword		42.00	Cft		
10	**Plain cement plaster ½" thick, 1:3, up to 20 ft height**					
a	For Signboard		84.00	Sft		
11	**White marble plaque with standard text, size 18"×22"×0.75"**					
a	White marble plaque with standard text, size 18"×22"×0.75"		5.50	Sft		
	Grand Total Inclusive of All Govt Applicable Taxes, Transpotations and Installation					